


P.O. Box 665 – 117 West Main Street  
Hahira, GA 31632

Phone: 229-585-9018  
E-mail:  
mail@altmanbarrettarchitects.com



# **Letter of Transmittal**

**TO: Plan Holders**

**FROM: Travis Petitjean**

**DATE: 10/20/2022**

**SUBJECT:** Addendum 1  
HVAC Replacement for Westside Elementary School  
Houston County School District

**WE ARE SENDING YOU:**

- Enclosed
- Prints
- Change order
- 2 Pages via EMAIL (including cover)**
- Specifications

**ENCLOSED:**


<b><u>COPIES</u></b>	<b><u>DATE</u></b>	<b><u>DESCRIPTION</u></b>
1	10/20/2022	Addendum 1

**Transmitted as checked below:**

- For your use**
- As requested
- For your information
- For review & comment
- No exceptions taken
- Exceptions noted
- Resubmit

**REMARKS:**

**COPY :** A+B File 22023 / A-1



**HVAC REPLACEMENT FOR  
WESTSIDE ELEMENTARY SCHOOL  
201 N. PLEASANT HILL ROAD  
WARNER ROBINS, GA 31093  
HOUSTON COUNTY SCHOOL DISTRICT**

**ADDENDUM NO. 1**  
**October 20, 2022**

**REVISIONS TO THE SPECIFICATIONS:**

None

**REVISIONS TO THE DRAWINGS:**

1. Sheet A1000:
  - a. General Renovation Notes:
    - i. Add the following: "3. Contractor shall take all precautions to prevent damage to existing lawn and landscaping during the project. All disturbed areas shall be properly filled with topsoil and seeded to establish groundcover. Landscaping needing removal for access to existing units shall be coordinated with the Owner's representative and removal is the responsibility of the Contractor."
2. Sheet A2101:
  - a. Detail 2/A2101:
    - i. At Note 2 at OHP-1, add the following: "Contractor shall replace existing HVAC pad with new 4" thick concrete pad. Minimum size shall be 30 square feet."

**END**